



“प्राकृतिक सम्पदा युक्त हराभरा सहर, सम्पूर्ण नगरबासीको एउटै रहर”

परशुराम नगरपालिका

# नगर कार्यपालिकाको कार्यालय



पत्र संख्या :- २०८०/०८१  
चलानी नम्बर :- १९०८

जोगबुडा, डडेल्धुरा  
सुदूरपश्चिम प्रदेश, नेपाल

## दररेट पेश गर्ने सम्बन्धी सूचना

प्रकाशित मिति: २०८३/०१/१६

- परशुराम नगरपालिकाको स्वीकृत वार्षिक कार्यक्रम अनुसार तपसिल बमोजिमको कार्यका लागि ईच्छुक निर्माण व्यवसायीबाट सिलबन्दी दररेट माग गरी निर्माण कार्य गर्नुपर्ने भएकोले यो सूचना प्रकाशित भएको मितिले सात दिनभित्र सिलबन्दी दररेट यस परशुराम नगरपालिकाको कार्यालयमा पेश गर्नु हुन सम्बन्धित
- सबैलाई यो सूचना प्रकाशित गरिएको छ।

क्र. स.	विवरण	जम्मा रकम (मु. अ. क. बाहेक)	दररेट पेश गर्ने अन्तिम समय
१.	वडा कार्यालय तार जाली घेरवार तथा गेट निर्माण पनपा २ बसौटी	२५७९३९.५७	२०८३/०१/२३ कार्यालय समयभित्र

- दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नवीकरण भएको फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपि, नवीकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजतपत्र) प्रमाणपत्रको प्रतिलिपि, मु. अ. क. दर्ता प्रमाणपत्रको प्रतिलिपि र आर्थिक वर्ष २०८१/०८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपि संगलग्न गरी सिलबन्दी खाममा पेश गर्नु पर्नेछ।
- उक्त कार्यको लागि आवश्यक BoQ (Bill of Quantity) यस कार्यालयको वेबसाइट <http://www.parshurammun.gov.np> बाट डाउनलोड गर्न सकिनेछ।
- BoQ मा आफूले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट रूपमा बुझिने गरी लेखेर पेश गर्नुपर्नेछ। केरमेट भएको दररेट (BoQ) मूल्यांकनमा समावेश गरिने छैन।

खगेन्द्र साउंद

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत

फोन: ०९६४११००४, फ्याक्स: ०९६४११००४

ईमेल: parshurammun@gmail.com, वेबसाइट: <http://www.parshurammun.gov.np>



Parshuram Municipality  
Office Of Municipal Executive  
Sudurpaschim Province, Nepal  
Jogbuda, Dadeldhura



ROO

योजनाको नाम : बडा कार्यालय तार जाती घेरवार तथा गेट निर्माण पनपा ०२ बसौटी

Location :Parshuram Municipality-02, Dadeldhura

Item.No	Description	Unit	Quantity	Rate in figure	Rate in words	Amount
1	Earthwork in excavation in Boulder mixed and Soft soil in foundation, trenches including timbering and shoring & 30m Lead and 1.5 m. lift all complete as per design, drawing and specification.	cum	7.723			
2	Stone soling work in foundation and floors with supplying of approved quality of stone laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification.	cum	1.840			
3	Plain Cement Concrete ( P.C.C.) in 1:2:4 in foundation with cement, sand and crushed stone aggregate including mixing, laying, finishing to approved level, line and dimensions and curing all complete as per specification and direction.	cum	1.504			
4	50×50×5 Angle Fabrication ,Purchase,Installation GI Wire Fencing Complete All Task as per authority of site incharge including paint on angle pole all task complete as per site incharge.	KG	202.260			
5	Procurement and Supply of 10 SwG Heavy Coated GI Wiremesh of size 3"x3"	Sqm	60.000			
6	Knetting & Fencing (Fixing) Work of wiremesh by use angle plate and nut bolt all task complete.	Rm	60.000			
7	P.C.C.(1:1.5:3 ) for M20 R.C.C.work in foundation, columns, beams, slabs, lintels etc. with cement, sand, and crushed stone aggregate of size less than 20mm including mixing with concrete mixture, compacting the concrete with vibrator machine, laying, finishing to approved level ,lines and dimensions and curing all complete nett.	cum	2.430			
8	Steel reinforcement bar (grade 415 or above) tested including straightening, cleaning, cutting, bending and fixing in position with 20 B. G. annealed binding wire as per drawing and instruction complete work	kg	165.263			
9	Formwork with approved materials for all works necessary propping, scaffoldong, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for Column/Slab/Beam etc. complete work.	sqm	12.184			
10	Iron Compound Gate	kg	230.400			
<b>Sub-Total Amount</b>						
<b>Vat@13%</b>						
<b>Total Project Cost</b>						

Total Amount in words:

Name of firm:

Name of authorized person:

Address:

Date:

Sign:

Stamp